

Exhibit N

Preliminary Geotechnical Subsurface
Report, prepared by S&ME Engineers

REPORT OF GEOTECHNICAL EXPLORATION
FOR
SOWER BOULEVARD SITE
FRANKFORT, KENTUCKY
PROJECT NO. 1183-14-027
JULY 25, 2014

Prepared For

Commonwealth of Kentucky Finance and Administration Cabinet
Department for Facilities and Support Services
Division of Engineering and Contract Administration
403 Wapping Street, 1st Floor
Frankfort, Kentucky 40601

Prepared by
S&ME, Inc.
2020 Liberty Road, Suite 105
Lexington, Kentucky 40505

© S&ME, Inc., All Rights Reserved



July 25, 2014

Commonwealth of Kentucky Finance and Administration Cabinet
Department for Facilities and Support Services
Division of Engineering and Contract Administration
403 Wapping Street, 1st Floor
Frankfort, Kentucky 40601

Attention: Mr. Andy Casebier, Architect

Subject: Report of Geotechnical Exploration
Sower Boulevard Site
Frankfort, Kentucky
S&ME Project Number 1183-14-027

Dear Mr. Casebier:


S&ME, Inc. has completed the preliminary geotechnical exploration for the development of the property at the south end of Sower Boulevard in Frankfort, Kentucky. The purpose of this preliminary exploration is to obtain a general understanding of the subsurface conditions at this site and to assist in project development and planning. A design phase (final) geotechnical exploration will be performed by the Developer for the final design. We conducted this project in general accordance with S&ME Proposal No. 11-1400041 dated April 29, 2014 which was authorized by Commonwealth of Kentucky Delivery Order DO2-785-14000012351. This report explains our understanding of the project, documents our findings, and presents our conclusions and geotechnical engineering considerations.

S&ME appreciates the opportunity to provide these services to the Kentucky Finance and Administration Cabinet. If you have any questions, please call.

Respectfully submitted,
S&ME, Inc.

Daniel Furgason
Daniel A. Furgason, P.E.
Senior Engineer
Kentucky License No. 25,646

Andrew M. Fiehler
Andrew M. Fiehler, P.E.
Project Engineer
Kentucky License No. 23,977



Attachments: Report of Geotechnical Exploration

2014 Projects / 1183-14-027 Report

REPORT OF GEOTECHNICAL EXPLORATION
Sower Boulevard Site
Frankfort, Kentucky
S&ME Project No. 1183-14-027

| | |
|---|-----------|
| 1.0 INTRODUCTION..... | 1 |
| 2.0 PROJECT INFORMATION..... | 1 |
| 2.1 Site Description | 1 |
| 2.2 Project Description | 2 |
| 3.0 SITE GEOLOGY | 2 |
| 4.0 EXPLORATION METHODS..... | 3 |
| 4.1 Field Exploration..... | 3 |
| 4.2 Laboratory Testing | 4 |
| 5.0 SUBSURFACE CONDITIONS..... | 4 |
| 5.1 General Soil Profile | 4 |
| 5.2 Groundwater | 5 |
| 6.0 LABORATORY TEST RESULTS..... | 5 |
| 7.0 GEOTECHNICAL CONSIDERATIONS..... | 6 |
| 8.0 FOLLOW UP SERVICES..... | 15 |
| 9.0 LIMITATIONS | 15 |

Important Information About Your Geotechnical Engineering Report (ASFE)

| | |
|------------|---------------------------------|
| Appendix A | Site Location/Topographic Map |
| | Boring Location Plan |
| Appendix B | Test Boring Record Legend |
| | Test Boring Records |
| | Field Testing Procedures |
| Appendix C | Summary of Laboratory Test Data |
| | Laboratory Testing Procedures |

REPORT OF GEOTECHNICAL EXPLORATION
Sower Boulevard Site
Frankfort, Kentucky
S&ME Project No. 1183-14-027

1.0 INTRODUCTION

S&ME, Inc. has completed the preliminary geotechnical exploration for the development of the property at the south end of Sower Boulevard, also known as the Carpenter Farm, in Frankfort, Kentucky. The purpose of this preliminary exploration is to obtain a general understanding of the subsurface conditions at this site and to assist in project development and planning. A design phase (final) geotechnical exploration will be performed by the Developer for the final design. We conducted this project in general accordance with S&ME Proposal No. 11-1400041 dated April 29, 2014 which was authorized by Commonwealth of Kentucky Delivery Order DO2-785-14000012351. This report explains our understanding of the project, documents our findings, and presents our conclusions and geotechnical engineering considerations.

The purpose of this preliminary exploration is to obtain a general understanding of the subsurface conditions at this site. This report explains our understanding of the project, documents our findings, and presents our conclusions and geotechnical engineering considerations.

2.0 PROJECT INFORMATION

2.1 Site Description

The project site is located at the southern end of Sower Boulevard in Frankfort, Kentucky. The property is approximately 34 acres. The Site Topographic and Boundary Survey performed by HDR, Inc., dated April 18, 2014 indicates the site slopes downhill from the high point at the southern property edge at an approximate elevation of 810 feet. The site slopes downhill from the high point to approximately 772 feet near the southwest corner, 758 feet near the northwest corner and 752 feet along the east edge of the property.

The site is undeveloped with mostly open field and pasture with a few scattered trees and a tree-lined fence row. Prior to performing the field work, the south-western third of the site was bushhogged to remove overgrown brush and briars. The remainder of the property was overgrown with waist high weeds and brush with scattered clusters of trees and tree lined fence rows.

At least five closed depressions, indicating possible karst conditions, were present on the site.

2.2 Project Description

The Commonwealth of Kentucky will solicit proposals from developers to design and construct a 334,100 square foot office building on the state owned land. The configuration of the building(s) has not been determined. Conceptual planning performed by Sherman/Carter/Barnhart Architects suggests a four to five story building, however, the developer and their design team will determine the final location and configuration of the office building(s) to meet the size specified. The new parking lot areas will have spaces for 1,330 vehicles.


Since the project is in the preliminary design stage, no additional drawings, site grading or structural loading are currently available.

3.0 SITE GEOLOGY

A review of the *Frankfort East Quadrangle, Franklin County, Kentucky*, developed by the USGS indicates the site is underlain by Upper Lexington Limestone and Tanglewood Limestone. The Upper Lexington Limestone consists of the Devils Hollow Member and the Millersburg Member. The Devils Hollow is generally dark blueish gray to tannish gray, weathering to light brownish gray, micro- to fine-grained limestone, with no fossils, very thin to thin bedded and interbedded with shale. The Millersburg is generally interbedded limestone (65 to 75 percent) and shale, medium light gray, very fine to coarse grained, contains many fossils and is irregularly bedded. The Tanglewood Limestone, present primarily on the north and east side of the site, is medium to dark gray, fine to coarse grained, with very thin to thin beds and contains many small fossils.

While cavities and sink holes are common in the Tanglewood Limestone, the formation is more notable for an erratic bedrock surface and the development of soil filled, solution widened slots in the bedrock. At least two of our borings, borings B-20 and B-45, encountered such slots in the bedrock. Boring B-20 falls on an approximate line with the mapped sinkholes. Boring B-45 is also near a mapped sinkhole.

The map below shows the USGS mapped sink holes on the site. Most of the site is an area considered with a high potential for karst development. The southwest area of the site is generally indicated to have a moderate potential for karst development.



No faults are mapped on the USGS mapping in the area of the site. Regional dip across the site is relatively flat.

4.0 EXPLORATION METHODS

The procedures used by S&ME for field and laboratory sampling and testing are in general accordance with ASTM procedures and established engineering practice. Appendix B contains brief descriptions of the procedures used in this exploration.

4.1 Field Exploration

Andrew Fiehler, P.E., of S&ME visited the site to observe pertinent site features, surface indications of the site geology, to log the borings, and to direct drilling operations. A total of 88 soil test borings were advanced for this exploration. The borings were numbered B-1 through B-88. The boring locations and elevations were determined by an S&ME survey crew. Please note that our survey crew checked several spot elevations from the HDR survey to verify agreement. While most of the elevations were in agreement, a discrepancy of about three feet was noted with the benchmark iron pin at the end of Sower Boulevard with a noted elevation of 778.54 feet. Figure 2 in Appendix A shows the locations of the borings.

The borings were advanced using a track-mounted Deidrich D-50 drill rig using 4 1/4-inch O.D. augers. The drillers obtained soil samples in the soil test borings using a split-barrel sampler driven by an automatic hammer system in general accordance with ASTM D1586. We also

obtained three relatively undisturbed Shelby tube samples using direct push methods. Rock coring was performed upon auger refusal at 12 of the boring locations. The stratification lines shown on the Test Boring Records represent the approximate boundaries between soil and/or rock surfaces. The transitions may be more gradual than shown.

4.2 Laboratory Testing

The S&ME engineer sealed and returned the soil samples to our laboratory where he assigned the applicable laboratory tests. These tests are used to determine the engineering properties of the soil. All soil samples were visually classified by the geotechnical engineer in general accordance with the Unified Soil Classification System (ASTM D2487). We conducted natural moisture content determinations and Atterberg limits tests on selected soil samples to aid in classification. We conducted a standard Proctor test on composite bulk samples from Borings B-40, B-52, B-75 and B-84. California Bearing Ratio (CBR) tests were performed on bulk soil samples obtained from Borings B-52 and B-84. Unconfined compressive strength tests were performed on relatively undisturbed Shelby tube soil samples from Borings B-8, B-19, and B-35. Unconfined compressive strength tests were performed on bedrock core samples from borings B-12, B-15, B-22, B-25, B-31, B-37, B-47, B-50, B-66, B-68, and B-81. The obtained laboratory data and descriptions of the tests are included in Appendix C.

5.0 SUBSURFACE CONDITIONS

5.1 General Soil Profile

Our borings initially penetrated from 1 to 12 inches of topsoil (average 5.5 inches) underlain by low plasticity Lean Clay (CL) to a depth of up to 6.0 feet (average depth of 2.6 feet). The Lean Clay was brown, generally firm to very stiff with trace amounts of oxide nodules. The Lean Clay was soft at borings B-21, B-37 and B-65. Lean Clay was not encountered at five of the borings. Below the lean clay and topsoil high plasticity Fat Clay (CH) was encountered and extended to the weathered limestone horizon. The Fat Clay (CH) was brown to dark brown, generally firm to hard with trace amounts of oxide nodules. Chert fragments were observed in samples at a few locations. The Fat Clay was encountered to a depth of 30 feet at Borings B-45, and included limestone floaters from 6.0 to 15.0 feet, and was soft below a depth of 15.0 feet. No Fat Clay was encountered in Borings B-19, B-46 or B-48.

Below the clay, 0.2 to 3.6 feet (average 0.7 feet) of weathered limestone was encountered beginning at depths of 0.2 to 31.0 feet (Elevation 803.2 to 749.8 feet). Auger refusal, interpreted to be limestone, was encountered at depths of 0.5 to 32.2 feet (Elevation 802.7 to 748.6 feet). The depth to weathered rock could extend deeper than the auger refusal depth.

Limestone bedrock was cored to depths of 9.0 to 11.7 feet at 12 of the boring locations. The rock was generally light gray and fine to medium grained with Rock Quality Designation (RQD) of 31 to 100 percent. RQD values of 21 and 0 percent were measured in the top two feet of rock core at Borings B-63 and B-68. The RQD at Boring B-81 varied from 17 to 80 percent. One or more thin clay seams were observed in the cored rock at most of the borings where rock was cored. Small, minor solution cavities were observed in the limestone at Boring B-22.

Please refer to the Test Boring Records in Appendix B for details.

5.2 Groundwater

Groundwater seepage was not observed in any of the borings during drilling and all of the borings were dry upon completion of augering. The borings were backfilled with auger cuttings after the completion of drilling. As such, 24-hour water levels were not measured.

6.0 LABORATORY TEST RESULTS

Natural moisture contents of the low plasticity lean clay ranged from 3.7 to 34.7 percent. Atterberg limit tests of the lean clay indicated liquid limits ranging from 47 to 49 percent with a plasticity index ranging from 25 to 29 percent. Natural moisture contents for the high plasticity fat clay ranged from 10.3 to 37.2 percent. Atterberg limit tests of the fat clay indicated liquid limits ranging from 63 to 75 percent with a plasticity index ranging from 35 to 48 percent.

Two standard Proctor tests of bulk sample indicated a maximum dry density of 98.0 and 97.1 pcf at an optimum moisture content of 22.7 and 24.3 percent, respectively. Two California Bearing Ratio (CBR) tests of the bulk sample materials indicated CBR values of 3.1 and 4.1 percent. Unconfined compression testing (Q_u) was performed on undisturbed samples at three borings. The locations of the samples and test results are included in Table 1, below.

Table 1
Soil Strength Test Results

| Boring | Depth (feet) | Soil Type | Q_u (psf) |
|--------|--------------|-----------|-------------|
| B-8 | 3.0 – 5.0 | CL | 2,698 |
| B-19 | 3.0 – 5.0 | CH | 1,562 |
| B-35 | 3.0 – 5.0 | CH | 5,346 |

Unconfined compression tests (Q_u) were also performed on representative rock core samples from each of the 12 borings with rock core. The locations of the samples and test results are included in Table 2, below and in the Laboratory Summary Sheets in Appendix C.

Table 2
Rock Core Strength Test Results

| Boring | Depth | Q_u (psi) |
|--------|-------------|-------------|
| B-12 | 7.3 – 7.9 | 6,382 |
| B-15 | 10.0 – 10.5 | 8,442 |
| B-22 | 8.7 – 9.3 | 5,469 |
| B-25 | 5.5 – 6.3 | 8,809 |
| B-31 | 9.4 – 9.8 | 6,049 |
| B-37 | 4.0 – 4.9 | 11,606 |
| B-47 | 2.6 – 3.1 | 16,495 |
| B-50 | 7.4 – 7.8 | 19,052 |
| B-63 | 18.0 – 18.4 | 6,887 |
| B-66 | 14.7 – 15.4 | 10,446 |
| B-68 | 7.6 – 8.0 | 8,562 |
| B-81 | 17.3 – 17.7 | 8,320 |

7.0 GEOTECHNICAL CONSIDERATIONS

We identified the following key issues that will impact the proposed site planning and construction:

Variable Rock Elevation - Foundations

Based on the anticipated loads for a multi-story building, foundations will likely be founded on bedrock. The bedrock is generally shallow thus we anticipate foundations bearing on bedrock; however the surface of the bedrock varies from an elevation 802.7 feet to 748.6 feet across the site. On a preliminary basis, we anticipate an allowable bearing pressure of 20 kips per square foot (ksf) to 50 ksf would be suitable for support of spread foundations on intact bedrock. This should be confirmed once foundation loads are available and more detailed analyses is performed. During foundation construction, 2-inch diameter probe holes should be drilled into the bedrock to allow for observation of the continuity of the bedrock. If seams or voids are observed in the bedrock, additional excavation may be required.

Karst Conditions

Sink holes were observed on the site and have been previously mapped as shown in Section 3.0 of this report. At least two of our borings encountered soil filled, solution widened slots in the bedrock. Additional investigation and remediation should be performed on these areas prior to construction. Boring B-45 was located adjacent to a previously mapped sink hole shown in the existing parking area northeast of the site. Soft, deep weak soils were encountered at this location.

Buildings should be sited away from known sinkholes. S&ME recommends the building not be constructed in the vicinity of Boring B-45 unless deep foundations, extended to bedrock are used. Consideration should also be given to siting the building either southwest or northeast of a line between borings B-20 and B-79. Pavement areas are often constructed over remediated sinkholes areas.

Additional exploration is needed to delineate the extent of the potential sinkholes at the site. Delineation of sinkholes can be accomplished by several methods including:

- Drilling a series of closely spaced rock soundings in an X pattern across the mapped depressions.
- Excavating test pits an X pattern across the mapped depression to expose the bedrock surface.
- Using geophysical testing, primarily electrical resistivity, to map the subsurface conditions.

Each of these approaches has their strong and weak points. Drilling soundings is a relatively inexpensive approach but requires that the drill rig be able to access the depression. Steep slopes may prevent access to portions of several of the depressions. Inferences of the bedrock profile must also be made between the sounding locations. While excavating test pits allows for a visual examination of the subsurface, excavating equipment has a limited reach. If the bedrock depth is beyond the extent of the equipment sufficient information may not be obtained. Electrical resistivity testing can provide a detailed profile of the subsurface with no visual impact to the site. Karst features can also be delineated after the topsoil has been stripped; however, waiting until earthwork has begun does not aid in site planning or budgeting for repair of sinkholes.

Prior to placing soil fill is also an opportune time to remediate sinkholes. Each sinkhole is unique and should be evaluated by an S&ME engineer who will provide recommendations for repair. Our experience indicates that one of the more cost effective means of repairing sinkholes

is to excavate the soil from the sinkhole area to expose the throat of the sinkhole and construct an inverted rock filter. An inverted rock filter consists of lining the sinkhole throat/excavation with filter fabric and backfilling the excavation with crushed stone starting with larger stone at the bottom and decreasing the size of the stone as the hole is filled. Typically the largest stone size used is rip-rap; however, we expect that the sinkholes at the site will be relatively shallow and may only require KYDOT #2 sized stone and smaller. Once the excavation is backfilled within about two feet of the surrounding grade, the filter fabric is folded over the top of the crushed stone and the area is capped with compacted clay.

High Plasticity Soils

Atterberg limits testing performed during this preliminary exploration indicate that the soil beginning at depths ranging from just below the topsoil to about five feet below the existing ground surface is comprised of high plasticity fat clay (CH). Soils with plasticity indices greater than 30 percent have a tendency to shrink and swell with changes in moisture content. The tested samples of the fat clay exhibited a plasticity index of 35 to 48 percent. Lightly loaded structural elements such as slabs-on-grade, sidewalks, pavement areas and non-load bearing walls are most susceptible to damage from shrinking and swelling soils. The final geotechnical exploration should include additional plasticity testing and swell testing to further define the engineering properties of the soil, and to determine the magnitude that the Fat Clay will impact development prior to implementing costly procedures to mitigate the plasticity issue.

Site Grading / Earthwork

The site grading operations will likely produce three distinct materials – soil, a soil/rock mixture, and shot rock. Each of these materials requires different methods for placement as structural fill.

Soil –Ideally, structural soil fill is defined as inorganic natural soil with a maximum particle size of 3 inches, plasticity index of 30 or less, and maximum dry density of at least 95 pounds per cubic foot (pcf) when tested by the standard Proctor method (ASTM D698). The standard Proctor tests performed indicate the on-site soils to have a maximum dry density of greater than 95 pcf; however, the plasticity index on two of the four samples exceeded 30 percent.

The fat clay encountered at the site is common throughout central Kentucky. Rather than wasting large volumes of soil that do not meet the structural fill criteria or importing soil that does meet these criteria in areas under building slabs and pavements, we recommend placing the higher plasticity soils in deeper fill areas (at least 3 feet below subgrade) and capping the fat clay with lean clay.

During construction, additional standard Proctor and Atterberg limits testing of fill soils should be performed to determine the moisture/density relationship and assess the plasticity of the soil prior to use as structural soil fill. Structural fill should be placed in relatively thin (6- to 8-inch) layers and compacted to at least 98 percent of the standard Proctor maximum dry density for the building pad and parking lot areas. The moisture content of the fill material should be maintained within 3 percent of optimum in order to obtain proper compaction.

In-place density testing must be performed on structural soil fill as a check that the previously recommended compaction criteria have been achieved. This allows our project engineer to monitor the quality of the fill construction and verify that his design criterion is being achieved in the field. We further recommend that these tests be performed on a full-time basis by S&ME. The testing frequency for density tests performed on a full-time basis can be determined by our personnel based on the area to be tested, the grading equipment used, and construction schedule. Tests should be performed at vertical intervals of one-foot or less as the fill is being placed. The on-site soils are sensitive to changes in moisture content, thus they will pump and rut during wet conditions. If grading operations are performed during periods of wet weather, these materials will not perform satisfactory during proofrolling. If soft or wet soils are encountered during the proofrolling observations, we recommend that the area be undercut to stiff native soils or stabilized in-place. Typical stabilization consists of undercutting/backfilling, placement of large crushed stone, or placement of geotextile/geogrid. Lime stabilization also works well and has the advantage of leaving the material in-place and reducing the potential for swell beneath slabs-on-grade. An alternative to wasting the wet clay soils is to temporarily stockpile this material for aeration and proper placement during dryer conditions. **As such, we highly recommend that earthwork be performed during the warm, dry summer months.**

Soil/Shot rock Mixture – The mass excavation will likely generate material that consists of both soil and rock. The soil/shot-rock mixture will be generated primarily during removal of the weathered rock zone and in mass rock excavations after blasting. Our experience is that compaction problems occur when the soil/shot-rock mix is placed using “normal rock placement procedures”. The soil/shot-rock mixture is a problematic material from an earthwork perspective, as it is difficult to compact. Soil/shot-rock should not be used as fill under the proposed structures.

Placing the soil/rock mix requires using modified soil fill procedures to reduce the potential for future problems. If the mix contains more than 15 percent soil, it should be placed using the

modified soil fill procedures described in this paragraph. For the soil/rock mix, the lift thickness should be maintained between 8 and 12 inches and the moisture content of the soil portion should be near the optimum moisture content or slightly above. The maximum particle size should be limited to 12 inches in any one dimension. A combination of tracked equipment, heavy rubber tired vehicles (haul trucks, scrapers, etc.), and a Caterpillar 815 or larger sheepsfoot compactor are typically adequate for placing this material. Approval of the lift placement and compaction will be determined by a S&ME engineer on the basis of the moisture content of the soil within the matrix, the blend of rock pieces, and the behavior of the fill material under the compactive effort. The goal is to minimize voids and to promote the breakdown of weak point-to-point contact of the rock pieces.

Shot rock – After the soil overburden and weathered rock zone has been removed, bedrock removal will likely be required. We anticipate that blasting will be required to remove most of the bedrock. Typically, blasting contractors will “overshoot” the rock to depths below the required elevations. As such, the blasted material will need to be removed to competent bedrock. **Any “heaved rock” resulting from blasting operations should be removed to expose the underlying undisturbed bedrock. “Heaved rock” is not adequate for supporting the proposed building, floor slabs, and/or pavement areas.**

The shot-rock material generated from bedrock excavation at the site can also be used as structural fill material, especially under the pavement areas. Shot-rock fill should not be used beneath the proposed building pads. Shot-rock fill is defined as clean shot-rock that contains less than 10 percent soil content. The following criteria are recommended for shot-rock fill construction:

- The subgrade must be free of ponded water and stable prior to and during shot-rock fill placement.
- Where additional soil fill is required to achieve the finished grades, the shot-rock fill should be covered with a non-woven geotextile filter fabric in order to reduce the potential for the migration of soil into the underlying shot-rock. Structural soil fill criteria and placement recommendations are outlined above.
- Shot-rock fill may be used up to the design subgrade elevation in pavement areas. If shot-rock fill is placed to the pavement subgrade elevation, we recommend that it be “choked off” with a thin (3 to 4 inch thick) layer of dense graded aggregate (DGA) prior to constructing the pavement section. The shot-rock fill should also contain sock covered, perforated pipes at least 4-inch diameter to inhibit water from building up beneath the pavement section. The drainage pipe should include a headwall at the outlet end, and

should drain to daylight away from the pavement area. Consider the use of a channel lined ditch at the end of the headwall to reduce erosion.

- Limit the maximum particle size to 12 inches in any one dimension.
- Shot-rock should have adequate smaller rock fragments to effectively "choke" the larger rock pieces by filling the voids or open spaces. The larger rock pieces should lie flat and not overlap each other. The percentage of soil in the fill should be limited to a maximum of 10 percent.
- Place the clean shot-rock fill in maximum 18-inch thick lifts. The actual lift thickness will vary as the particle size and soil content varies.
- Adequate compaction of shot-rock fill normally requires six to eight passes of heavy construction equipment on the fill surface. Typically, the equipment used consists of bulldozers and dump trucks. The geotechnical engineer should evaluate the suitability of the proposed compaction equipment and techniques. Approval of the lift placement and compaction will be determined by a S&ME engineer or geotechnician.

Monitoring of shot-rock must be done visually by an experienced geotechnician working directly and closely with one of our senior geotechnical engineers. Placement of shot-rock is a blend of art and science and the experience of the equipment operator and testing personnel are crucial to achieving the desired performance from the fill. Key indicators include material type, gradation, soil percentage and moisture content, equipment used to place the material, and how the fill material reacts to the equipment. The placement criteria will vary somewhat as the material varies. For example - as the soil content increases, the lift thickness should be decreased.

Site Grading / Site Selection

Site grading plans have not yet been developed. While the depth to weathered rock in the explored areas ranged from about 0.2 to 31.0 feet below existing grades the average depth was about 6 ½ feet. The site grading plan should take into account the following:

- Topsoil thickness ranged from 1 to 12 inches across the site.
- Highly plastic clay soils present at shallow depths.
- Cuts extending just a few feet below the existing ground surface will likely encounter rock in most areas. Rock excavation should be anticipated in utility excavations. If blasting is performed during building pad preparation, consider drilling and blasting to excavate a trench for underground utilities.
- Remediation of sink holes including excavation and filling with properly graded material.

- Elevations across the site vary by as much as 60 feet. We anticipate that free-standing retaining wall, terracing of the site, or a combination of both will be required.
- Depending on the grade selection, a deep rock cut (greater than 20 feet to 30 feet) is possible. If a deep cut is planned the cut slope should be further evaluated and designed by a geotechnical engineer. Fill slopes should also be evaluated by a geotechnical engineer.

Construction Accessibility / Site Degradation

Based on our on-site observations and our experience with similar soil conditions, construction accessibility will be problematic if attempted during cold/wet seasons of the year. Additionally, positive drainage should be maintained at all times during construction. The clay soils will become very soft if they are allowed to absorb water. Construction accessibility should be better during the hot/drier months of the year. During the wet periods, a construction road or pad consisting of a geo-textile fabric overlain by gravel may be required. Soft and/or wet areas may require selective undercutting, repair after construction is completed, or other treatment as recommended by the geotechnical engineer. We recommend that this site be graded and developed during warm, dry months of the year.

Pavement

General Discussion – Site development plans were not yet available; however, we understand that the project will require parking for 1,330 vehicles. Pavement design is a combination of traffic volume (both number and types of vehicles), the subgrade strength, and pavement materials (either asphalt or concrete). Once specific site development plans and grading plans are developed, a pavement design should be performed. For this preliminary exploration we performed two CBR tests of the on-site soils which indicated values of 3.1 percent and 4.1 percent. These results are common for soils throughout central Kentucky.

Flexible Asphalt Pavement – In order for pavement to perform satisfactorily, the subgrade soils must have sufficient strength and be stable enough to avoid deterioration from construction traffic and support the paving equipment. In addition, the completed pavement section must resist freeze/thaw cycles and wheel loads from traffic. Generally, construction traffic loading is more severe than the traffic after construction.

The preliminary pavement section given below is based on the assumption that the subgrade is prepared in accordance with the recommendations presented earlier in this report, and that any newly placed fill soils for the pavement subgrade have been compacted to at least 98 percent of

the standard Proctor maximum dry density at moisture contents ranging from ± 3 percent of the soil's optimum moisture content as determined by the standard Proctor test.

Minimizing infiltration of water into the subgrade and rapid removal of subsurface water are essential for the successful long-term performance of the pavement. Both the subgrade and the pavement surface should have a minimum slope of one-quarter inch per foot to promote surface drainage. Edges of the pavement should provide a means of water outlet by extending the aggregate base course through to side ditches. Side ditches should be at least 2 feet below the pavement surface.

The materials should conform and be placed and compacted in accordance with the applicable sections of the Kentucky Transportation Cabinet (KTC) Standard Specifications for Road and Bridge Construction, latest edition. We used the American Association of State Highway and Transportation Officials (AASHTO) Guide for Design of Pavement Structures (1993) as a basis for our flexible pavement thickness analysis. The total pavement thickness requirement is a function of the California bearing ratio (CBR). We performed CBR testing on two bulk samples of the on-site soils.

Specific traffic volume estimates were not available; however, we understand that parking for 1,330 vehicles will be required. We estimated the ESAL's for the development based on the anticipated daily traffic. The following pavement design recommendations are based on the assumptions of a 20 year service life, and 50,000 ESAL's for light duty pavement and 1,500,000 ESAL's for heavy duty pavement. Once site development plans are available, a specific pavement design should be performed.

S&ME recommends that the pavement section (base stone and asphalt) be placed after the majority of the new building construction has been completed. S&ME recommends that both binder and surface mix asphalt be placed sequentially before traffic is allowed on the new pavement. **S&ME recommends that the light duty pavement section be used for light automobile parking, and that the heavy duty pavement section be used for drive lanes and roadway.**

If construction sequencing requires that new pavement areas be constructed prior to substantial completion of the building, do not allow construction traffic on the finished pavement. The following pavement sections are based on our ESTIMATED traffic volumes. The sections listed below should be considered as ESTIMATES and used for general budgeting purposes only. A final design should be performed once the final design and use of the project are completed.

ESTIMATED Asphalt Pavement Bearing on Soil with a CBR Value of 3 percent – Maximum Asphalt Option

| MATERIAL | LIGHT DUTY | HEAVY DUTY | KY TRANSPORTATION CABINET SPECIFICATION |
|------------------------|------------|------------|---|
| Asphalt Surface Course | 1-½ Inches | 1-½ Inches | Section 400 |
| Asphalt Binder Course | 5 Inches | 9 Inches | Section 400 |
| Dense Graded Aggregate | 6 Inches | 9 inches | Section 303 |

ESTIMATED Asphalt Pavement Bearing on Soil with a CBR Value of 3 percent – Maximum Aggregate Option

| MATERIAL | LIGHT DUTY | HEAVY DUTY | KY TRANSPORTATION CABINET SPECIFICATION |
|------------------------|------------|------------|---|
| Asphalt Surface Course | 1-½ Inches | 1-½ Inches | Section 400 |
| Asphalt Binder Course | 3 Inches | 6 Inches | Section 400 |
| Dense Graded Aggregate | 10 Inches | 18 inches | Section 303 |

Depending on the final site grades, a significant volume of shot rock may be generated during site preparation. Placing shot rock at the pavement subgrade elevations would increase the CBR value and thus possibly allow for a reduction in the above estimated pavement sections.

S&ME should monitor the installation of the asphalt and base, check the installed thickness of the aggregate materials, and perform in-place density tests. Asphalt placement should be monitored full-time to observe placement and compaction procedures. Asphalt samples should be collected periodically and tested for asphalt cement content, aggregate gradation, and Marshall Density.

Impervious Concrete Pavement – We recommend that in areas where heavy, concentrated loads are expected (i.e. - dumpster area, entrances, etc.) concrete pavement section be used. For dumpster areas, we recommend that rigid pavement be extended beyond the dumpster pad for the entire length of the garbage truck. The pavement subgrade should be stabilized in accordance with the recommendations for the asphalt paved areas, and the related recommendations in this report. We recommend that the concrete pavement be supported by at least a 6 inch layer of compacted DGA. The DGA should be compacted to a minimum of 98 percent of the standard Proctor maximum dry density. We recommend a minimum concrete section of 8 inches for this site. The concrete should be air-entrained and have a 28-day compressive strength of 4,000 psi. Joint spacing should be at a maximum spacing of 15 feet each way.

Water Management

Management of both surface and subsurface water will be a key issue to development of the site. Subsurface water will tend to migrate toward the sink holes and other lower elevation areas of the site. The earthwork should be phased such that the swales are stabilized and are able to convey water away from the site while maintaining the integrity of the site.

Future Studies

The above items warrant further attention and should be addressed on a more detailed design phase exploration program. Additionally, the design phase geotechnical exploration should address the following:

- Additional plasticity testing and swell testing should be performed to define the potential impact of expansive clays.
- Once structural loading and site grading is determined, additional evaluation should be performed for foundation loading.
- Additional exploration should be performed to further investigate the sink holes on the site and to provide specific recommendations for remediation.
- Cut and/or fill slope stabilities should be evaluated once a site grading plan is developed.

We anticipate a site seismic classification of either “B” or “C” depending on the final building design. It is our experience that a site specific seismic evaluation could allow for a less conservative structural design and realized construction cost savings.

8.0 FOLLOW UP SERVICES

This report is preliminary and is not intended for final design purposes. Additional geotechnical work will be required once specific building locations, types, and grades have been established.

9.0 LIMITATIONS

This report has been prepared for the exclusive use of Commonwealth of Kentucky Finance and Administration Cabinet, Department for Facilities and Support Services for specific application to this project site. Our conclusions and recommendations have been prepared using generally accepted standards of geotechnical engineering practice in the Commonwealth of Kentucky. No other warranty is expressed or implied. This company is not responsible for the conclusions, opinions, or recommendations of others based on these data.

Our conclusions and recommendations are based on the design information furnished to us, the data obtained from the previously described preliminary geotechnical exploration, and our past experience. They do not reflect variations in the subsurface conditions that are likely to exist between our borings and soundings and in unexplored areas of the site. These variations result from the inherent variability of the general subsurface conditions in this geologic region.

We recommend that the Owner retain S&ME to continue our involvement in the project through the subsequent phases of design and construction. Our firm is not responsible for interpretation of the data contained in this report by others.

Important Information about Your Geotechnical Engineering Report

Subsurface problems are a principal cause of construction delays, cost overruns, claims, and disputes.

While you cannot eliminate all such risks, you can manage them. The following information is provided to help.

Geotechnical Services Are Performed for Specific Purposes, Persons, and Projects

Geotechnical engineers structure their services to meet the specific needs of their clients. A geotechnical engineering study conducted for a civil engineer may not fulfill the needs of a construction contractor or even another civil engineer. Because each geotechnical engineering study is unique, each geotechnical engineering report is unique, prepared *solely* for the client. No one except you should rely on your geotechnical engineering report without first conferring with the geotechnical engineer who prepared it. *And no one — not even you — should apply the report for any purpose or project except the one originally contemplated.*

Read the Full Report

Serious problems have occurred because those relying on a geotechnical engineering report did not read it all. Do not rely on an executive summary. Do not read selected elements only.

A Geotechnical Engineering Report Is Based on A Unique Set of Project-Specific Factors

Geotechnical engineers consider a number of unique, project-specific factors when establishing the scope of a study. Typical factors include: the client's goals, objectives, and risk management preferences; the general nature of the structure involved, its size, and configuration; the location of the structure on the site; and other planned or existing site improvements, such as access roads, parking lots, and underground utilities. Unless the geotechnical engineer who conducted the study specifically indicates otherwise, do not rely on a geotechnical engineering report that was:

- not prepared for you,
- not prepared for your project,
- not prepared for the specific site explored, or
- completed before important project changes were made.

Typical changes that can erode the reliability of an existing geotechnical engineering report include those that affect:

- the function of the proposed structure, as when it's changed from a parking garage to an office building, or from a light industrial plant to a refrigerated warehouse,

- elevation, configuration, location, orientation, or weight of the proposed structure,
- composition of the design team, or
- project ownership.

As a general rule, *always* inform your geotechnical engineer of project changes—even minor ones—and request an assessment of their impact. *Geotechnical engineers cannot accept responsibility or liability for problems that occur because their reports do not consider developments of which they were not informed.*

Subsurface Conditions Can Change

A geotechnical engineering report is based on conditions that existed at the time the study was performed. *Do not rely on a geotechnical engineering report* whose adequacy may have been affected by: the passage of time; by man-made events, such as construction on or adjacent to the site; or by natural events, such as floods, earthquakes, or groundwater fluctuations. *Always* contact the geotechnical engineer before applying the report to determine if it is still reliable. A minor amount of additional testing or analysis could prevent major problems.

Most Geotechnical Findings Are Professional Opinions

Site exploration identifies subsurface conditions only at those points where subsurface tests are conducted or samples are taken. Geotechnical engineers review field and laboratory data and then apply their professional judgment to render an opinion about subsurface conditions throughout the site. Actual subsurface conditions may differ—sometimes significantly—from those indicated in your report. Retaining the geotechnical engineer who developed your report to provide construction observation is the most effective method of managing the risks associated with unanticipated conditions.

A Report's Recommendations Are *Not* Final

Do not overrely on the construction recommendations included in your report. *Those recommendations are not final*, because geotechnical engineers develop them principally from judgment and opinion. Geotechnical engineers can finalize their recommendations only by observing actual

subsurface conditions revealed during construction. *The geotechnical engineer who developed your report cannot assume responsibility or liability for the report's recommendations if that engineer does not perform construction observation.*

A Geotechnical Engineering Report Is Subject to Misinterpretation

Other design team members' misinterpretation of geotechnical engineering reports has resulted in costly problems. Lower that risk by having your geotechnical engineer confer with appropriate members of the design team after submitting the report. Also retain your geotechnical engineer to review pertinent elements of the design team's plans and specifications. Contractors can also misinterpret a geotechnical engineering report. Reduce that risk by having your geotechnical engineer participate in prebid and preconstruction conferences, and by providing construction observation.

Do Not Redraw the Engineer's Logs

Geotechnical engineers prepare final boring and testing logs based upon their interpretation of field logs and laboratory data. To prevent errors or omissions, the logs included in a geotechnical engineering report should *never* be redrawn for inclusion in architectural or other design drawings. Only photographic or electronic reproduction is acceptable, *but recognize that separating logs from the report can elevate risk.*

Give Contractors a Complete Report and Guidance

Some owners and design professionals mistakenly believe they can make contractors liable for unanticipated subsurface conditions by limiting what they provide for bid preparation. To help prevent costly problems, give contractors the complete geotechnical engineering report, *but* preface it with a clearly written letter of transmittal. In that letter, advise contractors that the report was not prepared for purposes of bid development and that the report's accuracy is limited; encourage them to confer with the geotechnical engineer who prepared the report (a modest fee may be required) and/or to conduct additional study to obtain the specific types of information they need or prefer. A prebid conference can also be valuable. *Be sure contractors have sufficient time to perform additional study. Only then might you be in a position to give contractors the best information available to you, while requiring them to at least share some of the financial responsibilities stemming from unanticipated conditions.*

Read Responsibility Provisions Closely

Some clients, design professionals, and contractors do not recognize that geotechnical engineering is far less exact than other engineering disciplines. This lack of understanding has created unrealistic expectations that

have led to disappointments, claims, and disputes. To help reduce the risk of such outcomes, geotechnical engineers commonly include a variety of explanatory provisions in their reports. Sometimes labeled "limitations" many of these provisions indicate where geotechnical engineers' responsibilities begin and end, to help others recognize their own responsibilities and risks. *Read these provisions closely.* Ask questions. Your geotechnical engineer should respond fully and frankly.

Geoenvironmental Concerns Are Not Covered

The equipment, techniques, and personnel used to perform a *geoenvironmental* study differ significantly from those used to perform a *geotechnical* study. For that reason, a geotechnical engineering report does not usually relate any geoenvironmental findings, conclusions, or recommendations; e.g., about the likelihood of encountering underground storage tanks or regulated contaminants. *Unanticipated environmental problems have led to numerous project failures.* If you have not yet obtained your own geoenvironmental information, ask your geotechnical consultant for risk management guidance. *Do not rely on an environmental report prepared for someone else.*

Obtain Professional Assistance To Deal with Mold

Diverse strategies can be applied during building design, construction, operation, and maintenance to prevent significant amounts of mold from growing on indoor surfaces. To be effective, all such strategies should be devised for the *express purpose* of mold prevention, integrated into a comprehensive plan, and executed with diligent oversight by a professional mold prevention consultant. Because just a small amount of water or moisture can lead to the development of severe mold infestations, a number of mold prevention strategies focus on keeping building surfaces dry. While groundwater, water infiltration, and similar issues may have been addressed as part of the geotechnical engineering study whose findings are conveyed in this report, the geotechnical engineer in charge of this project is not a mold prevention consultant; *none of the services performed in connection with the geotechnical engineer's study were designed or conducted for the purpose of mold prevention. Proper implementation of the recommendations conveyed in this report will not of itself be sufficient to prevent mold from growing in or on the structure involved.*

Rely on Your ASFE-Member Geotechnical Engineer for Additional Assistance

Membership in ASFE/THE BEST PEOPLE ON EARTH exposes geotechnical engineers to a wide array of risk management techniques that can be of genuine benefit for everyone involved with a construction project. Confer with your ASFE-member geotechnical engineer for more information.




8811 Colesville Road/Suite G106, Silver Spring, MD 20910
Telephone: 301/565-2733 Facsimile: 301/589-2017
e-mail: info@asfe.org www.asfe.org

Copyright 2004 by ASFE, Inc. Duplication, reproduction, or copying of this document, in whole or in part, by any means whatsoever, is strictly prohibited, except with ASFE's specific written permission. Excerpting, quoting, or otherwise extracting wording from this document is permitted only with the express written permission of ASFE, and only for purposes of scholarly research or book review. Only members of ASFE may use this document as a complement to or as an element of a geotechnical engineering report. Any other firm, individual, or other entity that so uses this document without being an ASFE member could be committing negligent or intentional (fraudulent) misrepresentation.

APPENDIX A

SITE LOCATION/TOPOGRAPHIC MAP

BORING LOCATION PLAN



SCALE: 1" = 2000'

DATE: 6/27/2014

DRAWN BY: LHR


PROJECT NO: 1183-14-027



SOWER BOULEVARD SITE
 VICINITY MAP
 FRANKFORT, KENTUCKY

FIGURE NO.

1



LEGEND

Boring Location

⊕ B - X

SCALE: 1" = 200'

DATE: 7/9/2014

DRAWN BY: LHR

PROJECT NO:
1183-14-027



S&ME

WWW.SMEINC.COM
2020 LIBERTY ROAD, SUITE 105
LEXINGTON, KENTUCKY 40505
PHONE: 859-293-5518

**SOWER BOULEVARD SITE
BORING LOCATION PLAN
FRANKFORT, KENTUCKY**

FIGURE NO.

2

APPENDIX B

TEST BORING RECORDS LEGEND

TEST BORING RECORDS

FIELD TESTING PROCEDURES

TEST BORING RECORD LEGEND

FINE AND COARSE GRAINED SOIL INFORMATION

| COARSE GRAINED SOILS (SANDS & GRAVELS) | | FINE GRAINED SOILS (SILTS & CLAYS) | | | PARTICLE SIZE | |
|---|------------------|---------------------------------------|-------------|----------------------|---------------|---------------------------------|
| N | Relative Density | N | Consistency | Qu, KSF Estimated | | |
| 0-4 | Very Loose | 0-1 | Very Soft | 0-0.5 | Boulders | Greater than 300 mm (12 in) |
| 5-10 | Loose | 2-4 | Soft | 0.5-1 | Cobbles | 75 mm to 300 mm (3 to 12 in) |
| 11-20 | Firm | 5-8 | Firm | 1-2 | Gravel | 4.75 mm to 75 mm (3/16 to 3 in) |
| 21-30 | Very Firm | 9-15 | Stiff | 2-4 | Coarse Sand | 2 mm to 4.75 mm |
| 31-50 | Dense | 16-30 | Very Stiff | 4-8 | Medium Sand | 0.425 mm to 2 mm |
| Over 50 | Very Dense | Over 31 | Hard | 8+ | Fine Sand | 0.075 mm to 0.425 mm |
| | | | | | Silts & Clays | Less than 0.075 mm |

The **STANDARD PENETRATION TEST** as defined by ASTM D 1586 is a method to obtain a disturbed soil sample for examination and testing and to obtain relative density and consistency information. A standard 1.4-inch I.D./2-Inch O.D. split-barrel sampler is driven three 6-inch increments with a 140 lb. hammer falling 30 inches. The hammer can either be of a trip, free-fall design, or actuated by a rope and cathead. The blow counts required to drive the sampler the final two increments are added together and designate the N-value defined in the above tables.































ROCK PROPERTIES

| ROCK QUALITY DESIGNATION (RQD) | | ROCK HARDNESS | |
|--------------------------------|-----------|------------------|--|
| Percent RQD | Quality | | |
| 0-25 | Very Poor | Very Hard: | Rock can be broken by heavy hammer blows. |
| 25-50 | Poor | Hard: | Rock cannot be broken by thumb pressure, but can be broken by moderate hammer blows. |
| 50-75 | Fair | Moderately Hard: | Small pieces can be broken off along sharp edges by considerable hard thumb pressure; can be broken with light hammer blows. |
| 75-90 | Good | Soft: | Rock is coherent but breaks very easily with thumb pressure at sharp edges and crumbles with firm hand pressure. |
| 90-100 | Excellent | Very Soft: | Rock disintegrates or easily compresses when touched; can be hard to very hard soil. |

| Length of Rock Core Recovered | | X100 | Core Diameter | | Inches |
|-------------------------------|---|------|---------------|--------|--------|
| Recovery = | Length of Core Run | | BQ | NQ | HQ |
| | | | 63 REC | 1-7/16 | |
| | | | NQ | 1-7/8 | |
| | | | 43 RQD | 2-1/2 | |
| RQD = | Sum of 4 in. and longer Rock Pieces Recovered | X100 | | | |
| | Length of Core Run | | | | |

SYMBOLS








KEY TO MATERIAL TYPES

| | | | |
|---|--|--|---|
|  Topsoil |  High Plasticity Inorganic Silt or Clay |  Peat |  Amphibolite |
|  Asphalt |  Organic Silts/Clays |  Limestone |  Metagraywacke |
|  Crushed Limestone |  Well-Graded Gravel |  Sandstone |  Phyllite |
|  Fill Material |  Poorly-Graded Gravel |  Siltstone | |
|  Shot-rock Fill |  Silty Gravel |  Claystone | |
|  Low Plasticity Inorganic Silt |  Clayey Gravel |  Weathered Rock | |
|  High Plasticity Inorganic Silt |  Well-Graded Sand |  Dolomite | |
|  Low Plasticity Inorganic Clay |  Poorly-Graded Sand |  Granite | |
|  High Plasticity Inorganic Clay |  Silty Sand |  Gneiss | |
| Low Plasticity Inorganic Silt or Clay | Clayey Sand | Schist | |

SOIL PROPERTY SYMBOLS

| | |
|--------------|---|
| N: | Standard Penetration, BPF |
| M: | Moisture Content, % |
| LL: | Liquid Limit, % |
| PI: | Plasticity Index, % |
| Qp: | Pocket Penetrometer Value, TSF |
| Qu: | Unconfined Compressive Strength Estimated Qu, TSF |
| γ_d : | Dry Unit Weight, PCF |
| F: | Fines Content |

SAMPLING SYMBOLS

| | |
|---|--|
|  Undisturbed Sample |  No Sample Recovery |
|  Split-Spoon Sample |  Water Level After Drilling |
|  Rock Core Sample |  Extended Time Reading |
|  Auger or Bag Sample | |







TEST BORING RECORD

BORING NO: **B-1**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 765.3 | BORING STARTED: 6/4/2014 | | BORING COMPLETED: 6/4/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | BLOWS /6" | |
|-------------|----------------|----------------|--|---|-------------|---------------|---------|----|--|----|----|----|----|--------------|------------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 765.3 | 0 | Topsoil- 8 inches |  | | | | | | | | | | | |
| | 764.6 | | Lean Clay (CL) with trace oxide nodules, very stiff, brown, moist |  | | 13 | | | | | • | | | | 5 - 7 - 6 |
| | 763.3 | | Fat Clay (CH) with chert fragments, hard, brown to dark brown, moist |  | | 10 | | | | | | • | | | 4 - 5 - 21 |
| | 761.1 | | Weathered limestone |  | | 0 | | | | | | | | • | 50/4 |
| | 760.8 | 5 | Auger Refusal at 4.5 feet | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | 10 | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |








TEST BORING RECORD

BORING NO: **B-2**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 764.8 | BORING STARTED: 6/4/2014 | | BORING COMPLETED: 6/4/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | | BLOWS /6" |
|-------------|----------------|----------------|--|---|-------------|---------------|---------|----|--|----|----|----|----|----|--------------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 764.8 | 0 | Topsoil- 10 inches |  | | | | | | | | | | | |
| | 764.0 | | Lean Clay (CL) with trace oxide nodules, stiff, brown, moist |  | | 16 | | | | | • | | | | 6 - 7 - 8 |
| | | | |  | | 15 | | | | | • | | | | 6 - 6 - 7 |
| | 760.8 | | Fat Clay (CH) with chert fragments, very stiff, brown to dark brown, moist |  | | 16 | | | | | • | | | | 3 - 4 - 13 |
| | 758.6 | 5 | Weathered limestone |  | | 2 | | | | | | | | • | 50/0.2 |
| | 758.1 | | Auger Refusal at 6.7 feet | | | | | | | | | | | | |
| | | 10 | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |

CRAIG2 1183-14-027.GPJ QOR CORP.GDT 7/24/14











TEST BORING RECORD

BORING NO: **B-3**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 759.7 | BORING STARTED: 6/4/2014 | | BORING COMPLETED: 6/4/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | BLOWS /6" | |
|-------------|----------------|----------------|---|---|---|---------------|---------|----|--|----|----|----|----|--------------|-------------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 759.7 | 0 | Topsoil- 12 inches |  |  | 15 | | | | | • | | | | 5 - 6 - 6 |
| | 758.7 | | Fat Clay (CH) with trace oxide nodules, stiff, brown to dark brown, moist |  |  | 18 | | | | | • | | | | 7 - 6 - 8 |
| | 755.7 | 5 | Fat Clay (CH) with chert fragments, hard, brown to dark brown, moist |  |  | 18 | | | | | • | | | | 6 - 8 - 10 |
| | 753.7 | | Weathered limestone |  |  | 9 | | | | | | | | | • 23 - 50/2 |
| | 752.5 | | Auger Refusal at 7.2 feet | | | | | | | | | | | | |
| | | 10 | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |

PRG2 1183-14-027.GPJ QOR_QOR.GDT 7/24/14



TEST BORING RECORD

BORING NO: **B-4**

| | | |
|---------------------------------|--------------------------|----------------------------|
| PROJECT: Sower Boulevard | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | |
| ELEVATION: 761.8 | BORING STARTED: 6/4/2014 | BORING COMPLETED: 6/4/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | BLOWS /6" |
|-------------|-------------|-------------|--|-----------|-------------|---------------|---------|----|-------------------------------------|------------|
| | 761.8 | 0 | Topsoil- 6 inches | | | | | | | |
| | 761.3 | | Lean Clay (CL) with trace oxide nodules, stiff, brown, moist | | | 12 | | | | 5 - 5 - 5 |
| | | | | | | 18 | | | | 5 - 4 - 6 |
| | 757.8 | 5 | Fat Clay (CH) with trace oxide nodules, very stiff, brown to dark brown, moist | | | 16 | | | | 4 - 4 - 7 |
| | 755.3 | | Fat Clay (CH) with chert fragments, very stiff, brown to dark brown, moist | | | 18 | | | | 7 - 9 - 12 |
| | | | | | | 18 | | | | 5 - 7 - 8 |
| | 751.3 | 10 | Weathered limestone | | | | | | | |
| | 748.7 | | Auger Refusal at 13.1 feet | | | | | | | |
| | | 15 | | | | | | | | |
| | | 20 | | | | | | | | |

CRAIG 1183-14-027.GPJ QOR_CORP.GDT 7/24/14



TEST BORING RECORD

BORING NO: **B-5**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 772.2 | BORING STARTED: 6/4/2014 | | BORING COMPLETED: 6/4/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | | BLOWS /6" |
|-------------|-------------|-------------|---|-----------|-------------|---------------|---------|----|-------------------------------------|----|----|----|----|----|-----------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 772.2 | 0 | Topsoil- 6 inches | | | 8 | | | | | | | | | 3 - 4 - 5 |
| | 771.7 | | Lean Clay (CL) with trace oxide nodules, stiff, brown, moist | | | | | | | | | | | | |
| | 770.7 | | Fat Clay (CH) with trace oxide nodules, stiff, brown to dark brown, moist | | | 16 | | | | | | | | | 5 - 5 - 5 |
| | 769.7 | | Fat Clay (CH) with chert fragments, stiff, brown to dark brown, moist | | | | | | | | | | | | |
| | | | | | | 18 | | | | | | | | | 3 - 5 - 7 |
| | 766.9 | 5 | Weathered limestone | | | | | | | | | | | | |
| | 765.7 | | Auger Refusal at 6.5 feet | | | | | | | | | | | | |
| | | 10 | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |








CRAIG2 1183-14-027.GPJ QOR CORP.GDT 7/24/14



TEST BORING RECORD

BORING NO: **B-6**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 765.7 | BORING STARTED: 6/4/2014 | | BORING COMPLETED: 6/4/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |
| Remarks: | | | |

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | BLOWS /6" | |
|-------------|----------------|----------------|---|---|-------------|---------------|---------|----|---|---|------|
| | | | | | | | | | 01020304050 | | |
| | 765.7 | 0 | Topsoil- 8 inches |  | | | | | | | |
| | 765.0 | | Lean Clay (CL) with trace oxide nodules, stiff, brown, moist |  | | 12 | | |  | 5 - 5 - 6 | |
| | 763.7 | | Fat Clay (CH) with trace oxide nodules, very hard, brown to dark brown, moist |  | | 8 | | |  | 5 - 5 - 5 | |
| | 761.4 | | Weathered limestone |  | | 2 | | | |  | 50/3 |
| | 760.7 | 5 | Auger Refusal at 5 feet | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |

CRAIG2 1183-14-027.GPJ QOR_CORP.GDT 7/24/14



TEST BORING RECORD

BORING NO: **B-7**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 765.8 | BORING STARTED: 6/5/2014 | | BORING COMPLETED: 6/5/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | | BLOWS /6" |
|-------------|----------------|----------------|--|-----------|-------------|---------------|---------|----|-------------------------------------|----|----|----|----|----|--------------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 765.8 | 0 | Topsoil- 10 inches | | | 14 | | | | | | | | | 4 - 4 - 5 |
| | 765.0 | | Lean Clay (CL) with trace oxide nodules, stiff, brown, moist | | | 16 | | | | | | | | | 4 - 5 - 8 |
| | 762.3 | | Fat Clay (CH) with trace oxide nodules, very stiff, brown to dark brown, moist | | | 10 | | | | | | | | | 3 - 8 - 50/1 |
| | 760.8 | 5 | Weathered limestone | | | | | | | | | | | | |
| | 760.3 | | Auger Refusal at 5.5 feet | | | | | | | | | | | | |
| | | 10 | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |

CRA/G2 1183-14-027.GPJ QOR CORP.GDT 7/24/14



TEST BORING RECORD

BORING NO: **B-8**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 770.8 | BORING STARTED: 6/5/2014 | | BORING COMPLETED: 6/5/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | BLOWS /6" |
|-------------|-------------|-------------|--|-----------|-------------|---------------|---------|----|-------------------------------------|------------|
| | 770.8 | 0 | Topsoil- 11 inches | | | 12 | | | | 5 - 6 - 4 |
| | 769.9 | | Lean Clay (CL) with trace oxide nodules, stiff, brown, moist | | | 14 | | | | 5 - 5 - 7 |
| | 765.8 | 5 | Fat Clay (CH) with chert fragments, very stiff, brown to dark brown, moist | | | 6 | | | | 11 - 8 - 7 |
| | 763.8 | | Weathered limestone | | | | | | | |
| | 762.7 | | Auger Refusal at 8.1 feet | | | | | | | |
| | | 10 | | | | | | | | |
| | | 15 | | | | | | | | |
| | | 20 | | | | | | | | |

CRAIGZ 1183-14-027.GPJ QOR_CORP.GDT 7/24/14



TEST BORING RECORD

BORING NO: **B-9**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 769.2 | BORING STARTED: 6/5/2014 | | BORING COMPLETED: 6/5/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | HAMMER: AUTO | |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | BLOWS /6" |
|-------------|-------------|-------------|---|-----------|-------------|---------------|---------|----|-------------------------------------|-----------|
| | 769.2 | 0 | Topsoil- 5 inches | | | | | | | |
| | 768.8 | | Lean Clay (CL) with trace oxide nodules, stiff, brown, moist | | | 12 | | | | 6 - 7 - 6 |
| | | | | | | 12 | | | | 5 - 6 - 6 |
| | | 5 | | | | 16 | | | | 5 - 4 - 5 |
| | 763.2 | | Fat Clay (CH) with trace oxide nodules, stiff, brown to dark brown, moist | | | 18 | | | | 4 - 5 - 8 |
| | 759.9 | 10 | Weathered limestone | | | 6 | | | | 3 - 50/3 |
| | 758.5 | | Auger Refusal at 10.7 feet | | | | | | | |
| | | 15 | | | | | | | | |
| | | 20 | | | | | | | | |







TEST BORING RECORD

BORING NO: **B-10**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: -412,206.0 | BORING STARTED: 6/5/2014 | | BORING COMPLETED: 6/5/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | BLOWS /6" | |
|-------------|----------------|----------------|---|---|-------------|---------------|---------|----|--|----|----|----|----|--------------|--------------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 764.3 | 0 | Topsoil- 8 inches |  | | 13 | | | | | | | | | 4 - 6 - 6 |
| | | | Lean Clay (CL) with trace oxide nodules, stiff, brown, moist |  | | 16 | | | | | | | | | 3 - 4 - 7 |
| | 761.0 | 5 | Fat Clay (CH) with trace oxide nodules, stiff, brown to dark brown, moist |  | | 18 | | | | | | | | | 4 - 5 - 6 |
| | 758.0 | | Weathered limestone |  | | 10 | | | | | | | | | 8 - 6 - 50/3 |
| | 756.9 | | Auger Refusal at 8.1 feet | | | | | | | | | | | | |
| | | 10 | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |

CRAIG2 1183-14-027.GPJ QOR CORP.GDT 7/24/14

CRAIG 1183-14-027.GPJ QOR CORP.GDT 7/24/14






TEST BORING RECORD

BORING NO: **B-11**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 774.2 | BORING STARTED: 6/5/2014 | | BORING COMPLETED: 6/5/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | | BLOWS /6" |
|-------------|----------------|----------------|---|---|-------------|---------------|---------|----|--|----|----|----|----|----|--------------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 774.2 773.8 | 0 | Topsoil- 5 inches Lean Clay (CL) with trace oxide nodules, very stiff, brown, moist |  | | 10 | | | | | | | | | 8 - 4 - 5 |
| | 772.2 | | Fat Clay (CH) with chert fragments, stiff, brown to dark brown, moist |  | | 7 | | | | | | | | | 4 - 5 - 50 |
| | 770.9 770.5 | | Weathered limestone Auger Refusal at 3.7 feet |  | | | | | | | | | | | |
| | | 5 | | | | | | | | | | | | | |
| | | 10 | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |

RAIG2 1183-14-027.GPJ QOR_CORP.GDT 7/24/14

CRAIG2 1183-14-027.GPJ QOR_CORP.GDT 7/24/14



TEST BORING RECORD

BORING NO: **B-12**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 773.2 | BORING STARTED: 6/5/2014 | | BORING COMPLETED: 6/5/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | BLOWS /6" |
|-------------|-------------|-------------|---|-----------|-------------|---------------|---------|----|-------------------------------------|-----------|
| | | | | | | | | | 0 10 20 30 40 50 | |
| | 773.2 | 0 | Topsoil- 8 inches | | | | | | | |
| | 772.7 | | Lean Clay (CL) with trace oxide nodules, stiff, brown, moist | | | 16 | | | | 4 - 5 - 5 |
| | | | | | | 11 | | | | 4 - 5 - 9 |
| | 770.2 | | Fat Clay (CH) with trace oxide nodules, stiff, brown to dark brown, moist | | | | | | | |
| | 769.6 | | Weathered limestone | | | | | | | |
| | 769.2 | | Auger Refusal at 4 feet / Begin Coring | | | | | | | |
| | | 5 | Limestone, light gray, fine to medium grained | | | | | | | |
| | | | Water stained to 6 feet | | | 60/60 | 53 | | | |
| | | | Few thin clay seams to 8 feet | | | | | | | |
| | | 10 | | | | | | | | |
| | | | | | | 60/60 | 90 | | | |
| | | | | | | | | | | |
| | 759.2 | | Coring Terminated at 14 feet | | | | | | | |
| | | 15 | | | | | | | | |
| | | | | | | | | | | |
| | | 20 | | | | | | | | |

CRAIG2 1183-14-027.GPJ OOR_CORP.GDT 7/24/14



TEST BORING RECORD

BORING NO: **B-13**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 770.3 | BORING STARTED: 6/5/2014 | | BORING COMPLETED: 6/5/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | | BLOWS /6" |
|-------------|-------------|-------------|---|-----------|-------------|---------------|---------|----|-------------------------------------|----|----|----|----|----|---------------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 770.3 | 0 | Topsoil- 6 inches | | | | | | | | | | | | |
| | 769.8 | | Lean Clay (CL) with trace oxide nodules, very stiff, brown, moist | | | 14 | | | | | | | | | 3 - 4 - 7 |
| | | | | | | 18 | | | | | | | | | 6 - 7 - 10 |
| | 766.8 | | Fat Clay (CH) with trace oxide nodules, stiff, brown to dark brown, moist | | | | | | | | | | | | |
| | | | | | | 10 | | | | | | | | | 6 - 14 - 50/1 |
| | 765.0 | 5 | Weathered limestone | | | | | | | | | | | | |
| | 764.8 | | Auger Refusal at 5.5 feet | | | | | | | | | | | | |
| | | 10 | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |

CRAIG 1183-14-027.GPJ QOR CORP-GDT 7/24/14



TEST BORING RECORD

BORING NO: **B-14**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 769.6 | BORING STARTED: 6/5/2014 | | BORING COMPLETED: 6/5/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | HAMMER: AUTO | |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | | BLOWS /6" |
|-------------|-------------|-------------|---|-----------|-------------|---------------|---------|----|-------------------------------------|----|----|----|----|----|-----------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 769.6 | 0 | Topsoil- 6 inches | | | | | | | | | | | | |
| | 769.1 | | Lean Clay (CL) with trace oxide nodules, firm, brown, moist | | | 12 | | | | • | | | | | 3 - 4 - 4 |
| | | | | | | 10 | | | | • | | | | | 4 - 5 - 6 |
| | 766.1 | | Fat Clay (CH) with trace oxide nodules, stiff, brown to dark brown, moist | | | 18 | | | | • | | | | | 5 - 4 - 7 |
| | 763.6 | | Weathered limestone | | | | | | | | | | | | |
| | 763.2 | | Auger refusal at 6.4 feet | | | | | | | | | | | | |
| | | 10 | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |

CRAIG2 1183-14-027.GPJ QOR_CORP.GDT 7/24/14



TEST BORING RECORD

BORING NO: **B-15**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 777.2 | BORING STARTED: 6/5/2014 | | BORING COMPLETED: 6/5/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | | BLOWS /6" |
|-------------|----------------|-------------|---|-----------|-------------|---------------|---------|----|-------------------------------------|----|----|----|----|----|-----------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 777.2 776.8 | 0 | Topsoil- 5 inches | | | 18 | | | | | | | | | 2 - 3 - 4 |
| | | | Lean Clay (CL) with trace oxide nodules, firm, brown, moist | | | | | | | | | | | | |
| | 775.2 | | Fat Clay (CH) with trace oxide nodules, stiff, brown to dark brown, moist | | | 4 | | | | | | | | | 2 - 4 - 6 |
| | 773.9 773.5 | | Weathered limestone | | | | | | | | | | | | |
| | | | Auger Refusal at 3.7 feet / Begin Coring | | | | | | | | | | | | |
| | | 5 | Limestone, light gray, fine to medium grained | | | | | | | | | | | | |
| | | | | | | 58/60 | 32 | | | | | | | | |
| | | 10 | | | | | | | | | | | | | |
| | | | | | | 60/60 | 83 | | | | | | | | |
| | 763.5 | | Coring Terminated at 13.7 feet | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |

CRAIG2 1183-14-027.GPJ OOR_CORP.GDT 7/24/14



TEST BORING RECORD

BORING NO: **B-16**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 775.6 | BORING STARTED: 6/6/2014 | | BORING COMPLETED: 6/6/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |
| Remarks: | | | |

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | BLOWS /6" |
|-------------|-------------|-------------|--|-----------|-------------|---------------|---------|----|-------------------------------------|-----------|
| | 775.6 | 0 | Topsoil- 6 inches | | | | | | | |
| | 775.1 | | Lean Clay (CL) with trace oxide nodules, firm, brown, moist | | | 10 | | | | 3 - 4 - 3 |
| | 774.4 | | Fat Clay (CH) with trace oxide nodules, hard, brown to dark brown, moist | | | 4 | | | | 50/4 |
| | 773.7 | | Weathered limestone | | | | | | | |
| | 772.6 | | Auger Refusal at 3 feet | | | | | | | |
| | | 5 | | | | | | | | |
| | | 10 | | | | | | | | |
| | | 15 | | | | | | | | |
| | | 20 | | | | | | | | |

CRAIG2 1183-14-027.GPJ OOR CORP.GDT 7/24/14



TEST BORING RECORD

BORING NO: **B-17**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 775.6 | BORING STARTED: 6/6/2014 | | BORING COMPLETED: 6/6/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | | BLOWS /6" |
|-------------|-------------|-------------|---|-----------|-------------|---------------|---------|----|-------------------------------------|----|----|----|----|----|-----------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 775.6 | 0 | Topsoil- 8 inches | | | 14 | | | | | | | | | 4 - 4 - 5 |
| | 774.9 | | Lean Clay (CL) with trace oxide nodules, stiff, brown, moist | | | 18 | | | | | | | | | 5 - 6 - 8 |
| | 771.6 | 5 | Fat Clay (CH) with chert fragments, stiff to firm, brown to dark brown, moist | | | 16 | | | | | | | | | 4 - 5 - 7 |
| | | | | | | 18 | | | | | | | | | 3 - 3 - 4 |
| | 766.3 | | Weathered limestone | | | 4 | | | | | | | | | 50/4 |
| | 765.2 | 10 | Auger Refusal at 10.4 feet | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |

CRAIG2 1183-14-027.GPJ QOR CORP.GDT 7/24/14



TEST BORING RECORD

BORING NO: **B-18**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 778.3 | BORING STARTED: 6/6/2014 | | BORING COMPLETED: 6/6/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | | BLOWS /6" |
|-------------|-------------|-------------|--|-----------|-------------|---------------|---------|----|-------------------------------------|----|----|----|----|----|--------------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 778.3 | 0 | Topsoil- 4 inches | | | | | | | | | | | | |
| | 778.0 | | Lean Clay (CL) with trace oxide nodules, firm, brown, moist | | | 8 | | | | | | | | | 4 - 6 - 6 |
| | | | | | | 6 | | | | | | | | | 3 - 3 - 5 |
| | 775.3 | | Fat Clay (CH) with trace oxide nodules, firm, brown to dark brown, moist | | | | | | | | | | | | |
| | | | | | | 12 | | | | | | | | | |
| | 773.1 | 5 | Weathered limestone | | | | | | | | | | | | 3 - 4 - 50/2 |
| | 772.6 | | Auger Refusal at 5.7 feet | | | | | | | | | | | | |
| | | 10 | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |

CRAIG 1183-14-027.GPJ QOR_CORP.GDT 7/24/14



TEST BORING RECORD

BORING NO: **B-19**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 777.4 | BORING STARTED: 6/6/2014 | | BORING COMPLETED: 6/6/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | | BLOWS /6" |
|-------------|-------------|-------------|---|-----------|-------------|---------------|---------|----|-------------------------------------|----|----|----|----|----|-----------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 777.4 | 0 | Topsoil- 8 inches | | | | | | | | | | | | |
| | 776.7 | | Lean Clay (CL) with trace oxide nodules, firm, brown, moist | | | 16 | | | | • | | | | | 4 - 4 - 5 |
| | | | | | | 5 | | | | • | | | | | 3 - 3 - 5 |
| | 774.4 | | Auger Refusal at 3 feet | | | 0 | | | | | | | | • | 50/0 |
| | | 5 | | | | | | | | | | | | | |
| | | 10 | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |



TEST BORING RECORD

BORING NO: **B-20**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 775.5 | BORING STARTED: 6/6/2014 | | BORING COMPLETED: 6/6/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | BLOWS /6" |
|-------------|-------------|-------------|---|-----------|-------------|---------------|---------|----|-------------------------------------|--------------|
| | 775.5 | 0 | Topsoil- 4 inches | | | 14 | | | | 3 - 3 - 4 |
| | 775.2 | | Lean Clay (CL) with trace oxide nodules, firm, brown, moist | | | 18 | | | | 4 - 5 - 4 |
| | 771.5 | 5 | Fat Clay (CH) with chert fragments, firm to stiff, brown to dark brown, moist | | | 18 | | | | 3 - 3 - 5 |
| | | | | | | 18 | | | | 4 - 6 - 7 |
| | | 10 | | | | 18 | | | | 4 - 5 - 8 |
| | | 15 | | | | 6 | | | | 30 - 50/1 |
| | | 20 | | | | 16 | | | | 3 - 4 - 5 |
| | 750.5 | 25 | Weathered limestone | | | 10 | | | | 4 - 6 - 50/3 |
| | 750.3 | | Auger Refusal at 25.2 feet | | | | | | | |
| | | 30 | | | | | | | | |

CRAN2 1183-14-027.GPJ OOR_CORP.GDT 7/24/14







TEST BORING RECORD

BORING NO: **B-21**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 774.1 | BORING STARTED: 6/6/2014 | | BORING COMPLETED: 6/6/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | | BLOWS /6" |
|-------------|----------------|----------------|--|---|-------------|---------------|---------|----|--|----|----|----|----|----|--------------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 774.1 | 0 | Topsoil- 6 inches |  | | | | | | | | | | | |
| | 773.6 | | Lean Clay (CL) with trace oxide nodules, soft, brown, moist |  | | 14 | | | | • | | | | | 1 - 2 - 1 |
| | 772.6 | | Fat Clay (CH) with trace oxide nodules, firm, brown to dark brown, moist |  | | 16 | | | | • | | | | | 2 - 2 - 5 |
| | 770.1 | | Auger Refusal at 4 feet |  | | 0 | | | | | | | | • | 50/0 |
| | | 5 | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | 10 | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |

0RAIG2 1183-14-027.GPJ QOR_CORP.GDT 7/24/14

CRAIGZ 1183-14-027.GPJ QOR CORP.GDT 7/24/14















TEST BORING RECORD

BORING NO: **B-22**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 783.8 | BORING STARTED: 6/6/2014 | | BORING COMPLETED: 6/6/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | ROD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | | BLOWS /6" |
|-------------|----------------|----------------|--|---|-------------|---------------|---------|----|--|----|----|----|----|----|--------------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 783.8 | 0 | Topsoil- 6 inches |  | | | | | | | | | | | |
| | 783.3 | | Lean Clay (CL) with trace oxide nodules, firm, brown, moist |  | | 8 | | | | • | | | | | 3 - 4 - 4 |
| | 781.8 | | Fat Clay (CH) with trace oxide nodules, firm, brown to dark brown, moist |  | | 6 | | | | • | | | | | 2 - 3 - 2 |
| | | | |  | | 6 | | | | • | | | | | 3 - 3 - 6 |
| | | 5 | |  | | | | | | | | | | | |
| | 778.0 | | Weathered limestone |  | | | | | | | | | | | |
| | 777.8 | | Auger Refusal at 6 feet / Begin Coring | | | | | | | | | | | | |
| | | | Limestone, light gray, fine to medium grained |  | | | 33/48 | 31 | | | | | | | |
| | | | Water stained / minor solutioning to 10.5 feet |  | | | | | | | | | | | |
| | | 10 | |  | | | | | | | | | | | |
| | | | |  | | | | | | | | | | | |
| | | | |  | | | 57/60 | 42 | | | | | | | |
| | | | |  | | | | | | | | | | | |
| | 768.8 | 15 | Coring Terminated at 15 feet | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |

CRAIG2 1183-14-027.GPJ QOR_CORP.GDT 7/24/14



TEST BORING RECORD

BORING NO: **B-23**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 783.1 | BORING STARTED: 6/6/2014 | | BORING COMPLETED: 6/6/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | | BLOWS /6" |
|-------------|----------------|----------------|--|-----------|-------------|---------------|---------|----|-------------------------------------|----|----|----|----|----|---------------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 783.1 | 0 | Topsoil- 4 inches | | | 12 | | | | | | | | | 3 - 3 - 3 |
| | 782.8 | | Lean Clay (CL) with trace oxide nodules, firm, brown, moist | | | | | | | | | | | | |
| | 781.6 | | Fat Clay (CH) with trace oxide nodules, very stiff, brown to dark brown, moist | | | 10 | | | | | | | | | 3 - 4 - 15 |
| | 779.1 | | Fat Clay (CH) with chert fragments, hard, brown to dark brown, moist | | | 10 | | | | | | | | | 9 - 17 - 50/3 |
| | 778.1 | 5 | Weathered limestone | | | 2 | | | | | | | | | 50 |
| | 775.3 | | Auger Refusal at 7.8 feet | | | | | | | | | | | | |
| | | 10 | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |

CRAIG 1183-14-027.GPJ QOR_CORP.GDT 7/24/14



TEST BORING RECORD

BORING NO: **B-24**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 779.5 | BORING STARTED: 6/6/2014 | | BORING COMPLETED: 6/6/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | HAMMER: AUTO | |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | BLOWS /6" |
|-------------|-------------|-------------|--|-----------|-------------|---------------|---------|----|-------------------------------------|------------|
| | 779.5 | 0 | Topsoil- 5 inches | | | | | | | |
| | 779.1 | | Lean Clay (CL) with trace oxide nodules, stiff, brown, moist | | | 14 | | | | 3 - 3 - 5 |
| | | | | | | 16 | | | | 5 - 5 - 15 |
| | 776.5 | | Fat Clay (CH) with trace oxide nodules, very stiff, brown to dark brown, moist | | | | | | | |
| | 775.5 | | Fat Clay (CH) with chert fragments, hard, brown to dark brown, moist | | | 3 | | | | 50/4 |
| | 775.0 | | Weathered limestone | | | | | | | |
| | 774.0 | 5 | Auger Refusal at 5.5 feet | | | | | | | |
| | | 10 | | | | | | | | |
| | | 15 | | | | | | | | |
| | | 20 | | | | | | | | |



TEST BORING RECORD

BORING NO: **B-25**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 781.1 | BORING STARTED: 6/6/2014 | | BORING COMPLETED: 6/6/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | | BLOWS /6" |
|-------------|-------------|-------------|---|-----------|-------------|---------------|---------|----|-------------------------------------|----|----|----|----|----|-----------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 781.1 | 0 | Topsoil- 6 inches | | | 6 | | | | | | | | | 3 - 4 - 4 |
| | 780.6 | | Lean Clay (CL) with trace oxide nodules, firm, brown, moist | | | | | | | | | | | | |
| | 779.1 | | Fat Clay (CH) with trace oxide nodules, stiff, brown to dark brown, moist | | | 6 | | | | | | | | | 2 - 3 - 8 |
| | | | | | | | 3 | | | | | | | | 50/3 |
| | 776.8 | | Weathered limestone | | | | | | | | | | | | |
| | 776.6 | 5 | Auger Refusal at 4.5 feet / Begin Coring | | | | | | | | | | | | |
| | | | Limestone, light gray, fine to medium grained | | | | | | | | | | | | |
| | | | | | | 58/60 | 57 | | | | | | | | |
| | | 10 | | | | | | | | | | | | | |
| | | | | | | 59/60 | 82 | | | | | | | | |
| | | 15 | Coring Terminated at 14.5 feet | | | | | | | | | | | | |
| | 766.6 | | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |

CRAIG2 1183-14-027.GPJ QOR CORP.GDT 7/24/14



TEST BORING RECORD

BORING NO: **B-26**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 781.4 | BORING STARTED: 6/7/2014 | | BORING COMPLETED: 6/7/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | BLOWS /6" |
|-------------|-------------|-------------|--|-----------|-------------|---------------|---------|----|-------------------------------------|-----------|
| | 781.4 | 0 | Topsoil- 8 inches | | | | | | | |
| | 780.7 | | Lean Clay (CL) with trace oxide nodules, stiff to firm, brown, moist | | | 12 | | | | 3 - 4 - 5 |
| | 778.9 | | Fat Clay (CH) with trace oxide nodules, firm, brown to dark brown, moist | | | 18 | | | | 4 - 3 - 4 |
| | 777.4 | | Fat Clay (CH) with chert fragments, stiff, brown to dark brown, moist | | | 18 | | | | 3 - 5 - 7 |
| | 774.4 | 5 | | | | 2 | | | | 50/3 |
| | 773.9 | | Weathered limestone | | | | | | | |
| | | | Auger Refusal at feet | | | | | | | |
| | | 10 | | | | | | | | |
| | | 15 | | | | | | | | |
| | | 20 | | | | | | | | |



TEST BORING RECORD

BORING NO: **B-27**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 778.6 | BORING STARTED: 6/7/2014 | | BORING COMPLETED: 6/7/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | BLOWS /6" |
|-------------|----------------|----------------|--|-----------|-------------|---------------|---------|----|--|--------------|
| | | | | | | | | | 0 10 20 30 40 50 | |
| | 778.6 | 0 | Topsoil- 8 inches | | | | | | | |
| | 777.9 | | Lean Clay (CL) with trace oxide nodules, stiff to very stiff, brown, moist | | | 18 | | | | 3 - 3 - 4 |
| | 776.1 | | Fat Clay (CH) with trace oxide nodules, hard, brown to dark brown, moist | | | 16 | | | | 4 - 4 - 25 |
| | 774.5 | | Weathered limestone | | | 4 | | | | 50/4 |
| | | 5 | | | | | | | | |
| | 772.8 | | Auger Refusal at 5.8 feet | | | | | | | |
| | | 10 | | | | | | | | |
| | | 15 | | | | | | | | |
| | | 20 | | | | | | | | |



TEST BORING RECORD

BORING NO: **B-28**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 780.0 | BORING STARTED: 6/7/2014 | | BORING COMPLETED: 6/7/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | | BLOWS /6" |
|-------------|-------------|-------------|--|-----------|-------------|---------------|---------|----|-------------------------------------|----|----|----|----|----|-----------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 780.0 | 0 | Topsoil- 4 inches | | | 18 | | | | | | | | | 3 - 4 - 5 |
| | 779.7 | | Lean Clay (CL) with trace oxide nodules, firm, brown, moist | | | 8 | | | | | | | | | 3 - 2 - 3 |
| | 777.0 | | Fat Clay (CH) with trace oxide nodules, firm, brown to dark brown, moist | | | 16 | | | | | | | | | 4 - 6 - 7 |
| | 774.0 | 5 | Weathered limestone | | | | | | | | | | | | |
| | 773.5 | | Auger Refusal at 6.5 feet | | | | | | | | | | | | |
| | | 10 | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |

CRAIG2 1183-14-027.GPJ QOR_CORP.GDT 7/24/14



TEST BORING RECORD

BORING NO: **B-29**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 777.4 | BORING STARTED: 6/7/2014 | | BORING COMPLETED: 6/7/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | BLOWS /6" |
|-------------|-------------|-------------|--|-----------|-------------|---------------|---------|----|-------------------------------------|------------|
| | 777.4 | 0 | Topsoil- 6 inches | | | | | | | |
| | 776.9 | | Lean Clay (CL) with trace oxide nodules, firm, brown, moist | | | 14 | | | | 3 - 4 - 4 |
| | 775.9 | | Fat Clay (CH) with trace oxide nodules, very stiff, brown to dark brown, moist | | | 14 | | | | 4 - 5 - 16 |
| | 773.6 | | Weathered limestone | | | | | | | |
| | 771.6 | 5 | Auger Refusal at 5.8 feet | | | | | | | |
| | | 10 | | | | | | | | |
| | | 15 | | | | | | | | |
| | | 20 | | | | | | | | |

CRAIG2 1183-14-027.GPJ QOR_CORP.GDT 7/24/14







TEST BORING RECORD

BORING NO: **B-30**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 783.4 | BORING STARTED: 6/7/2014 | | BORING COMPLETED: 6/7/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | | BLOWS /6" |
|-------------|----------------|----------------|--|--|-------------|---------------|---------|----|--|----|----|----|----|----|--------------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 783.4 | 0 | Topsoil- .5 inches |  | | | | | | | | | | | |
| | 782.9 | | Lean Clay (CL) with trace oxide nodules, firm, brown, moist |  | | 10 | | | | ● | | | | | 4 - 3 - 4 |
| | 781.4 | | Fat Clay (CH) with trace oxide nodules, firm, brown to dark brown, moist |  | | 10 | | | | ● | | | | | 6 - 6 - 1 |
| | 780.4 | | Weathered limestone |  | | | | | | | | | | | |
| | 779.9 | | Auger Refusal at 3.5 feet | | | | | | | | | | | | |
| | | 5 | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | 10 | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |



TEST BORING RECORD

BORING NO: **B-31**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 782.6 | BORING STARTED: 6/7/2014 | | BORING COMPLETED: 6/7/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | ROD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | BLOWS /6" |
|-------------|-------------|-------------|--|-----------|-------------|---------------|---------|----|-------------------------------------|---------------|
| | 782.6 | 0 | Topsoil- 6 Inches | | | 8 | | | | 4 - 4 - 4 |
| | 782.1 | | Lean Clay (CL) with trace oxide nodules, stiff, brown, moist | | | | | | | |
| | 780.6 | | Fat Clay (CH) with trace oxide nodules, hard, brown to dark brown, moist | | | 6 | | | | 4 - 26 - 50/3 |
| | 778.6 | | Weathered limestone | | | 1 | | | | 50/1 |
| | 778.4 | 5 | Auger Refusal at 4.2 feet / Begin Coring | | | | | | | |
| | | | Limestone, light gray, fine to medium grained | | | | | | | |
| | | | Water stained to 9 feet with few very thin mud seams | | | 55/60 | 45 | | | |
| | | 10 | | | | | | | | |
| | | | | | | 42/60 | 70 | | | |
| | 768.4 | 15 | Coring Terminated at 14.2 feet | | | | | | | |
| | | 20 | | | | | | | | |

CRAUG2 1183-14-027.GPJ QOR CORP.GDT 7/24/14







TEST BORING RECORD

BORING NO: **B-32**

| | | | |
|---------------------------------|--------------------------|-------------------------|----------------------------|
| PROJECT: Sower Boulevard | | JOB NO: 1183-14-027 | REPORT NO: |
| PROJECT LOCATION: Frankfort, KY | | | |
| ELEVATION: 783.7 | BORING STARTED: 6/7/2014 | | BORING COMPLETED: 6/7/2014 |
| DRILLING METHOD: 4" HSA | RIG TYPE: D-50 | | HAMMER: AUTO |
| GROUNDWATER (ft): Dry | | BORING DIAMETER (IN): 4 | SHEET 1 OF 1 |

Remarks:

| Groundwater | ELEV. (FT.) | DEPTH (FT.) | MATERIAL DESCRIPTION | Lithology | Sample Type | Recovery (in) | RQD (%) | Qu | STANDARD PENETRATION RESISTANCE (N) | | | | | BLOWS /6" | |
|-------------|----------------|----------------|---|--|-------------|---------------|---------|----|--|----|----|----|----|--------------|-----------|
| | | | | | | | | | 0 | 10 | 20 | 30 | 40 | 50 | |
| | 783.7 | 0 | Topsoil- 6 inches |  | | | | | | | | | | | |
| | 783.2 | | Lean Clay (CL) with trace oxide nodules, firm, brown, moist |  | | 14 | | | | • | | | | | 4 - 3 - 4 |
| | 781.7 | | Fat Clay (CH) with trace oxide nodules, stiff, brown to dark brown, moist |  | | 16 | | | | | • | | | | 2 - 4 - 9 |
| | 780.5 | | Weathered limestone |  | | | | | | | | | | | |
| | 780.1 | | Auger Refusal at 3.6 feet | | | | | | | | | | | | |
| | | 5 | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | 10 | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | |